



HERLONG STREET

TRANSPORTATION ENGINEERING

PROJECT DESCRIPTION

Herlong Street, in southern Columbia County, is a two-lane rural collector road that serves as an important East-West corridor. The County has planned to reconstruct the paving of this dirt road in two (2) phases.

NFPS provided the design and permitting for the road reconstruction of SW Herlong Street to convert the existing 4.1 mile dirt road to a paved road with improved drainage and shoulders. Other major items of work included major earthwork, drainage structures, and base and asphalt construction.

TOTAL CONTRACT FUNDING

The total FDOT contract amount for this Small County Outreach Program (SCOP) funded project including design, construction, and inspection was approximately:

\$2,525,000

PERFORMANCE PERIOD

180 Calendar Days

DAYS 1-30
<ul style="list-style-type: none"> • MOBILIZATION • MAINTENANCE OF TRAFFIC • SEDIMENT BARRIER • CLEARING & GRUBBING
DAYS 31-90
<ul style="list-style-type: none"> • REGULAR & BORROW EXCAVATION • SUBSOIL EXCAVATION • STABILIZING ROADWAY & SHOULDER
DAYS 91-150
<ul style="list-style-type: none"> • TURNOUT CONSTRUCTION • PIP & CULVERT INSTALLATION • ASPHALT-PAVING OPERATIONS
DAYS 151-180
<ul style="list-style-type: none"> • SIGNS & PAVEMENT MARKINGS • PERFORMANCE TURF & SOD

CLIENT REFERENCE

Columbia County BOCC
135 NE Hernando Ave, Ste 203
Lake City FL 32056

Kevin Kirby
Assistant County Manager
386-758-1005
kevin_kirby@columbiacounty.com

PROJECT MANAGER

Gregory G Bailey, PE
1450 SW State Road 47
Lake City FL 32025
386-752-4675
gbailey@nfps.net

SERVICES PROVIDED

- Roadway & Drainage Design
- Environmental Permitting
- Signing and Pavement Marking
- Bid Preparation and Negotiation
- Post Design Services

FJ40E05CCB

