



SW 59TH DRIVE TRANSPORTATION ENGINEERING

PROJECT DESCRIPTION

SW 59th Drive in south central Hamilton County, is a two-lane rural collector road that serves as an important East-West corridor connecting CR 158 at two (2) points creating a loop.

NFPS provided the design and permitting for the widening and resurfacing to convert 1.72 miles the existing dirt road to a paved road and improved drainage and resurface 1.87 miles of existing paved road.

TOTAL CONTRACT FUNDING

The total FDOT contract amount for this Small County Outreach Program (SCOP) funded project including design, construction, and inspection was approximately:

\$1,212,000

PERFORMANCE PERIOD

240 Calendar Days

DAYS 1-30

- MOBILIZATION
- MAINTENANCE OF TRAFFIC
- SEDIMENT BARRIER

DAYS 31-120

- CLEARING & GRUBBING
- REGULAR & BORROW EXCAVATION
- MILLING OPERATIONS
- TURNOUT CONSTRUCTION

DAYS 121-210

- PIPE & CULVERT INSTALLATION
- ASPHALT-PAVING OPERATIONS

DAYS 211-240

- SIGNS & PAVEMENT MARKINGS
- PERFORMANCE TURF & SOD

CLIENT REFERENCE

Hamilton County BOCC
207 NE First Street
Jasper FL 32052

Contact: Louie Goodin
County Coordinator
386-792-6639
hamiltoncounty@windstream.net

PROJECT MANAGER

Gregory G Bailey, PE
1450 SW State Road 47
Lake City FL 32025
Jacksonville FL 32216
386-752-4675
gbailey@nfps.net

SERVICES PROVIDED

- Roadway & Drainage Design
- Environmental Permitting
- Signing & Pavement Marking
- Bid Preparation and Negotiation
- Post Design Services

